

Kubatura prac podczyszczeniowych aktualizacja z 02.07.2020r

Lp.	Nr przekroju	Km	Powierzchnia przekroju [m2]	Średnia powierzchnia przekroju [m2]	Długość odcinka [m]	Kubatura [m3]
1	2	3	4	5	6	7
1.	1-1	11,700	34,62	34,62	100,0	3462
2.	1.1-1.1	11,830	16,06	25,34	30,0	760,20
				12,47	50,0	623,25
3.	2-2	11,880	8,87	8,19	50,0	409,25
4.	3-3	11,930	7,50	7,02	50,0	351,00
5.	4-4	11,980	6,54	6,07	50,0	303,50
6.	5-5	12,030	5,60	5,80	50,0	289,75
7.	6-6	12,080	5,99	7,06	50,0	353,00
8.	7-7	12,130	8,13	7,43	50,0	371,50
9.	8-8	12,180	6,73	6,76	50,0	337,75
10.	9-9	12,230	6,78	7,40	50,0	369,75
11.	10-10	12,280	8,01	7,01	50,0	350,25
12.	11-11	12,330	6,00	7,03	50,0	351,25
13.	12-12	12,380	8,05	7,66	50,0	382,75
14.	13-13	12,430	7,26	7,59	50,0	379,50
15.	14-14	12,480	7,92	6,94	50,0	347,00
16.	15-15	12,530	5,96	6,84	50,0	342,00
17.	16-16	12,580	7,72	7,81	50,0	390,25
18.	17-17	12,630	7,89	4,07	50,0	203,25
19.	18-18	12,680	0,24	1,14	50,0	57,00
20.	19-19	12,730	2,04	3,64	50,0	181,75
21.	20-20	12,780	5,23	6,79	50,0	339,25
22.	21-21	12,830	8,34	6,40	50,0	319,75

23.	22-22	12,880	4,45	0,40	50,0	319,75
				3,63	50,0	181,25
24.	23-23	12,930	2,80			
				2,61	50,0	130,50
25.	24-24	12,980	2,42			
				5,46	50,0	273,00
26.	25-25	13,030	8,50			
				10,43	50,0	521,25
27.	26-26	13,080	12,35			
				10,95	50,0	547,25
28.	27-27	13,130	9,54			
				20,12	50,0	1006,00
29.	28-28	13,180	30,70			
				30,16	20,0	603,20
30.	29-29	13,230	29,62			
					1500,0	14537
				rezerwa	%	0
				suma:		14537

INSPEKTOR NADZORU INWESTORSKIEGO

Jacek Gęgała
 upr. bud. GP-1 7342/61/TO/92
 upr. bud. GP-1 7342/62/TO/92